



News About Your Neighborhood



The City of Wixom 2010 Road Maintenance Program Sibley Court

8/18/2010 UPDATE

Construction will be starting on Sibley Court on Friday, August 20. The existing pavement will be removed, and existing base material excavated. A few short sections of curb and gutter will be removed and replaced to ensure there are no areas of standing water in the curb line. After excavation, the condition of the subgrade will be evaluated, and edge drain will be installed to facilitate positive drainage. A geogrid reinforcement layer will then be installed, followed by 8 inches of limestone aggregate being placed, graded, and compacted. Finally, the new asphalt surface will be installed in two lifts.

The above work is expected to take approximately two weeks, and will be completed by Labor Day weekend, subject to poor weather or any other unforeseen circumstances. Any lawn restoration and street sign replacement will take place after all roadwork is complete.

Traffic will be maintained at all times during construction, but delays will occur. During the excavation process, residents will have very limited access to their driveways. We recommend that neighbors coordinate sharing driveways during this time. Advanced notice will be given when your driveway access is going to be impacted by the construction.

We ask for your patience during construction. Additional information, including project updates and frequently asked questions, can be obtained from our website:

http://www.hrc-engr.com/project_sites/wixom

If you have any questions and/or concerns during construction, please contact:

City of Wixom

Department of Public Services
Deanna Murphy
49045 Pontiac Trail
Wixom, Michigan 48393
248-624-4664

Project Observer

Hubbell, Roth & Clark, Inc.
Bob Muhal
2285 Franklin Road, Suite 140
Bloomfield Hills, MI 48302
248-535-3376

Project Manager

Hubbell, Roth & Clark, Inc.
Joe Heintz
105 W. Grand River
Howell, Michigan 48843
248-454-6574